



Information Update


Biosolids Master Plan, PS15-01



April 2017
Operations Committee
Administration Committee



What are Biosolids?



Drivers for Biosolids Master Plan

- Biosolids require large capital and on-going costs
- Condition and seismic issues with Plant 2 digesters
- Previous Biosolids Master Plan completed in 2003
- Opportunity for greater resource recovery
- State requirement to divert organics in trash from landfills



Biosolids Costs

- Biosolids reuse / disposal
 - ~\$17 million /year
 - 12% of net operating requirements
- Biosolids-related capital projects
 - >\$500 million currently budgeted
 - 17% of total capital program
 - 28% of proposed budget update for 2017/18


Plant 1 Solids Facilities good with completion of current projects (P1-100 & P1-101)




Plant 2 digesters need replacement



Newport-Inglewood Fault Runs Through Plant No. 2/ Liquefaction Hazard Zone



Market Research



- Agriculture and Horticulture users
- 83 potential users contacted
- 36 meetings
- Samples of potential products showed to potential users
- Data collected to determine cost and capacity for various reuse options

Key Market Findings

- Bulk products to agriculture key component
 - California will require Class A for direct land application
 - Arizona expected continue to accept Class B into future
 - Class A provides more options, but not a goal by itself
- Horticulture markets are much smaller, but high quality products would be more valued






Plant 2 Biosolids Facilities

**Alternative
Selection**




End-to-End Alternative Combinations Evaluated

- 27 combinations of processing and products with end use



Screening narrowed to 3 alternatives



Tiebreaker Considerations


1. Diversity for biosolids program

- Plant 1 produces Class B biosolids – no plans to change
- Providing Class A at Plant 2 diversifies reuse options
- **Eliminated Baseline Mesophilic Class B Alternative**

2. Early mitigation for seismic risk


- All alternatives will meet seismic standards
- **TPAD Class A** addresses seismic risk after first project.
 - Maximizes life of existing digesters
 - Allows subsequent project to be delayed
 - Allows keep existing digesters if they can be rehabilitated

Layout of Proposed Facilities



TPAD Class A – Minimum Initial Project


- Initial project includes:
 - Six 110-ft digesters, 30 ft tall
 - Batch tanks for Class A (~\$25 million)
 - Sludge feed facility
 - Cooling system
 - Relocation of warehouse, collections yard
- Meets Class A without existing digesters, but with less gas production
- Construction cost \$194 million (2017)
- Total project cost \$419 million
 - Escalation to mid-point of construction
 - Non-construction costs
 - Contingency



Proposed Plant 2 Biosolids Projects

- Preparation Projects
 - Southwest Perimeter Screening, P2-125
 - Warehouse Relocation, P2-126
 - Collections Yard Relocation, P2-127
- TPAD Digester Facility at Plant 2, P2-128
- Digester P, Q, R, & S Replacement, P2-129
- Subsequent projects
 - Replace 3 existing small digesters
 - Demolish remaining digesters

Digester Replacement Construction Schedule






AquaCritox Demonstration Project Evaluation Study, Project No. SP-125-17

**Alternative
Selection**



AquaCritox

- Uses high heat and pressure
- Complex processes and equipment
- No existing full scale facilities
- Pilot plant in Valencia, Spain in progress



AquaCritox Demonstration Project Evaluation Study

- Report prepared by vendor (SCFI Group Limited)
 - Proposed a facility at Plant 2
 - Concept layouts, sizing developed
 - Construction and operating costs estimated
- Biosolids Master Plan consultant assigned to review report, technology, and economic case for a project



Conclusions from Review of SCFI Report



- Underlying technology is proven for other applications
- Significant operational concerns
 - Corrosion, scaling, material compatibility
 - Highly specialized equipment
 - Equipment reliability not known
 - Pilot plant has not been in continuous and reliable operation
- Life cycle costs reviewed

AquaCritox Demonstration Project Economics

Expense	SCFI	Biosolids Master Plan Consultant Costs and Comments	
Construction Cost (unescalated)	\$26,500,000	\$34,500,000	<ul style="list-style-type: none"> • Ground improvements • Building for process equipment
Operations & Maintenance (NPV)	\$19,700,000	\$46,600,000	<ul style="list-style-type: none"> • 24/7 Operator required
Repair and Replacement (NPV)	\$0	\$11,700,000	<ul style="list-style-type: none"> • 15-year equipment life assumed
Power Generated NPV	-\$6,000,000	-\$6,000,000	
Total NPV	\$40,200,000	\$86,800,000	
NPV Unit Cost, \$/ton	\$505	\$1,090	

For reference, unit cost for full digester replacement is \$540/ton, but at a much larger scale.

Recommendations

- Do not pursue a Demonstration Project at this time
- Visit pilot plant in Spain when SCFI reports consistent and continuous operation
- Continue to monitor for key concerns
- Staff will seek grant opportunities and operating partners